

Quality Assurance Statement

Kada

Our Quality Manual has been developed to meet the requirements of AS/NZS ISO 9001: 1998 to ensure the quality objectives of the client are achieved through systematic development, implementation and maintenance of procedures which affect quality.

As the project enters the manufacturing, delivery, and installation phase, Kada has several assessments and audits in place across all project phases to ensure a successful delivery. Generally they occur; pre-manufacture, pre-delivery ex manufacturer, at assembly stage of product in Auckland, pre-delivery on site, on arrival to site, and first, second and third stages of installation.

Typically they include:

- Pre-manufacture Audit; Kada provides client approved shop drawings to manufacturers, quantifying numbers and types of componentry. Manufacturers provide audited totals of product, for Kada to cross check and confirm.
- Pre-delivery ex Manufacturer; Manufacturers provide Kada with componentry totals, for auditing prior to leaving the factory.
- Assembly of product in Auckland; Factory team leader's quality check and audit components on arrival into Kada's Auckland assembly plant.
- Pre-Delivery onsite; The Kada factory performs a final quality check of assembled product, prior to delivery to site. Kada's QA team review and sign off goods prior to dispatch from factory.
- Onsite arrival; Kada's installation team commences assembly onsite, coordinating with Building Contractor and other services onsite.
- Onsite quality checks; As the componentry assembly commences the Project Manager / Architect and Client are invited to join the onsite quality reviews so that any minor changes to layout can be made.
- Installation 1st stage completion; Kada and the Project Manager / Architect inspect the completed installation. A list of remedials is drafted up and agreed upon. This list is issued to appropriate parties and actioned.
- Installation 2nd stage completion; Kada and the Project Manager / Architect conduct a second walk through and mark off completed remedials.
- Installation 3rd stage final completion; Kada, Architect / Designer/ Project Manager and Client conduct a final walk through and quality assurance check before Kada officially hands over to the client.

We state that we have all the required manufacturing, assembly, warehousing, distribution and site management resources available to meet the projected and installation timeframes for this project.